



Major Mare Island Water and Sewer Improvements

City of Vallejo - Vallejo Flood & Wastewater District Project will Bore Under Mare Island Strait

Vallejo, CA -- In mid-August, a key project to improve reliable water and sewer services, and support economic development on Mare Island, will break ground. Known as the Mare Island Sewer and Water Main Replacement Project, the estimated \$16 million project is anticipated to last until February 1, 2019.

Overview

Currently, sewer and drinking water pipes serve Mare Island residents and businesses through lines located underneath the Mare Island Causeway and a second location farther down the Strait. The new project will use a boring technique to pull the new pipelines through two borings underneath the Mare Island Strait 95 feet north of the bridge and 75 feet below the river bed. The project will increase capacity for Mare Island, and includes conduits for VallejoNet fiber optics and a recycled water main for future potential projects.

The existing 18-inch force main is a critical component of the District’s sanitary sewer collection and discharge system on Mare Island. It was built in 1974 and is in poor condition, with no ready access for monitoring and maintenance. The replacement sewer force main will be tunneled deep beneath the Mare Island Strait using horizontal directional drilling (HDD), and then will continue via an open trench through River Park. It will then cross the Mare Island Causeway to Harbor Way, where it will connect to an existing sewer line under Mare Island Way.

The City’s drinking water mains that serve Mare Island are also nearing the end of their useful lives. The 20-inch line farther down the strait will no longer be used. This project adds new dual 18-inch drinking water mains and fiber optic conduits contained in a single tunnel that is separate from the tunnel containing the sewer and recycled water pipes. The City will continue to use the existing 14-inch water pipe under the bridge. The tunnels for the water and sewer pipes will be about 15 feet apart.

All environmental reviews were completed and were adopted by the City Council (and District Board of Trustees) on April 11, 2017. The project was designed by GHD Inc. and will be performed by Garney Pacific Inc. Construction management will be provided by Covello, a Psomas Company.

Funding

The project is estimated to cost slightly under \$16 million. Both the City and the District will contribute more than \$7 million each, and a grant from the U.S. Environmental Protection Agency will contribute \$1.2 million.

Anticipated Noise, Traffic and Park Impacts

- Between September and early February, work hours will vary from 8 hours a day/5 days a week to 12 hours a day/6 days a week except as noted below.
- When the new pipe is pulled through the borings, work will occur around the clock for two days per bore. During those brief times, bright lights and generator noise will be evident.
- River Park will remain open during construction. The parking lot at Hichborn may have less parking spaces available than usual. There will be lots of equipment in the park staging area; it will be fenced off and secured. Park paths will be accessible, although some may have detours during construction.
- Later in the project there will be traffic lane closures on Mare Island Way, Harbor Way, and the Mare Island Causeway. There are no full street closures anticipated.

Residents and business owners with questions about the project should contact Ed O’Brien at 707-654-9622. Questions about park access should be addressed to the Greater Vallejo Recreation District at 707-648-4600.

* * * * *

Media Contacts

City of Vallejo
Joanna Altman, Assistant to the City Manager
707-648-4362 Joanna.Altman@CityofVallejo.net

Vallejo Flood & Wastewater District
Jennifer Kaiser, Public Information Officer
707-652-7812 JKaiser@VallejoWastewater.org