


**NOTES:**

1. MINIMUM SLOPE OF FLOWLINE IS  $S=0.005$
2. CL 2 AB THICKNESS SHALL BE EQUAL TO STREET SECTION, BUT IN NO CASE SHALL BE LESS THAN 8".
3. VALLEY GUTTERS SHALL NOT BE ALLOWED ON THROUGH STREETS.
4. PORTLAND CEMENT CONCRETE SHALL CONFORM TO "MINOR CONCRETE" OF THE CALTRANS STANDARD SPECIFICATIONS EXCEPT THAT THE CEMENT CONTENT SHALL BE A MINIMUM OF 6 SACKS OF CEMENT PER CUBIC YARD OF CONCRETE.



**CITY OF VALLEJO STANDARD DETAIL**

**STANDARD VALLEY GUTTER**

APPROVED BY:

DIRECTOR OF PUBLIC WORKS

DRAWING NO:

**3-11**

SCALE:  
NONE

DATE:  
09/13/11